



06/04/2021

Project:

C12414 - Canyon Breeze

From:

Tom Redditt Sales Agency-Phoenix

Bob Tully

10211 N. 32nd St.

Suite C3

Phoenix, AZ 85028-3843

(602)277-0805

(602)277-0805 (Contact)

Job Reference Number: 33829

6-SERIES ITEMS ARE NOT PART OF STANDARD VOLLRATH PROGRAMS AND DO NOT QUALIFY FOR THE FREE FREIGHT PROGRAM.

Payment - Standard payment terms are 50% with order, 35% prior to ship and 15% on net 30 days from Date of Invoice, unless otherwise agreed.

Pricing - All quoted prices to Buyer are valid for 90 days from the quoted date, after which time they are subject to change at Seller's discretion.

Storage Fees - In the event Buyer receipt of shipment is delayed 10 business days or more beyond the scheduled and agreed to date, Buyer shall compensate Seller \$100 per day per trailer for storage of completed goods or work in process whether stored at Seller's facility or an independent storage company's facility.

Change Fees - Any changes made by Buyer after Sellers receipt of purchase order and drawing sign off are subject to change fees determined and assessed at the discretion of Seller.

Expediting Fees - Seller will respond to requests to expedite fabrication and shipment on request. Expediting is subject to additional fees, which need to be agreed to and paid by Buyer.

Item Qty Description List Each Discount Net Each Net Total

Initial:

1 1 ea 4-SERIES, SERVING SYSTEMS

\$16,877.07

50/10 \$7,594.68

\$7,594.68

Vollrath Model No. C12414_2 89" x30" Hot Station

- * Stainless Steel Construction
- * No Skirting
- * 4" Casters (2 Locking Casters)
- * Stainless Steel Base Finish
- * Stainless Corner Guards
- * Open Storage on Server Side
- * All Controls on Server Side
- * 14 Gauge Stainless Steel Countertop
- * 18 Gauge Plate Rest (Two Piece Construction)
- SERVER SIDE
- * Equipment Installed in Countertop (See

Accessory Details for Pricing & Spec)

* Contemporary Cafeteria Breath Guard with 6"

Pass Through Area on Operator Right

- * NO LIGHTS OR HEAT
- * Single Point Electrical Connection

1 ea 3640650 Hot Food Well Unit, Drop-In, electric, \$5,014.30 50/10 \$2,256.44 \$2,256.44

(4) 12" x 20" individual 20 gauge stainless steel insulated wells, 54-3/4"W x 26"D x 21-1/2"H (overall), wet operation only, individual infinite controls mounted in panel with cord, power indicator light, drip-free flange, 1" copper manifold drain with individual well shutoffs & manifold shutoff, 18 gauge stainless steel top, 18 gauge galvanized exterior housing, includes positioning clips, 2500 watts, 120v/60/1-ph, 20.8 amps, cord with NEMA 5-30P, NSF, cULus, Made in USA (54"W x 25-1/4"D cutout size, requires 7/8" corner radius)

Total for item 1

\$9,851.12

				00,04,202		
Item	Qty	Description	List Each	Discount	Net Each	Net Total
2	1 ea	4-SERIES, SERVING SYSTEMS Vollrath Model No. C12414_2 64" x30" Frost Top Station	\$18,436.71	50/10	\$8,296.52	\$8,296.52
		* Stainless Steel Construction * No Skirting * 4" Casters (2 Locking Casters) * Stainless Steel Base Finish * Stainless Corner Guards * Open Storage on Server Side * All Controls on Server Side * 14 Gauge Stainless Steel Countertop * 18 Gauge Plate Rest - SERVER SIDE * Equipment Installed in Countertop (See Accessory Details for Pricing & Spec) * Contemporary Single Sided with Top Shelf Buffet Breath Guard * NO LIGHTS OR HEAT * Single Point Electrical Connection				
	1 ea	FC-4C-03120-F Frost Top, Drop-In, self contained refrigeration, 3-pan, 300 series stainless steel, recessed drip flange with drain, remote on/off switch, 1/3 hp compressor, 120v/60/1-ph, 7.8 amps, NEMA 5-15P, overall dimensions: 41-1/2" x 26-1/16", cutout dimensions: 40-3/4" x 25-1/4", display area length: 35-1/2", cULus, NSF, Made in USA (contact Vollrath for lead time)	\$6,749.40	50/10	\$3,037.23	\$3,037.23
		·	otal for item 2	2	·	\$11,333.75

Michael Komendat

Product and Project Development Manager – Serving Systems & Components

THE VOLLRATH CO., LLC

1236 N. 18th Street, Sheboygan, WI 53081

O: 585.337.3855

mkomendat@vollrathco.com | vollrathcompany.com

Acceptance:	Date:	
Printed Name:		
Project Grand Total: \$21,184.87		

Grand Total

Initial: _____

\$21,184.87